LIGHTING FIXTURE SCHEDULE

PROVIDED FOR INFORMATION ONLY.
VERIFY AND INSTALL PER ELECTRICAL DRAWING

[THIS INFORMATION WAS PROVIDED BY THE OWNER & THE CONTRACTOR SHALL COORDINATE w/ THE PANDA EXPRESS CONSTRUCTION MANAGER ANY CONFLICTS WITH MODEL NUMBERS OR AVAILABILITY.]

07-04-2013

ITEM	SYMBOL	DESCRIPTION	QTY.	MFR. & CAT. NO.	REMARK
INTERIOR LIGHTING ITEM					
L1	L1	EDGE-LIT LED PANEL 120-277V UE - UNIVERSAL VOLTAGE	5	MANUFACTURER: LSI FIXTURE: SPF24-LED-50-UE-DIM-35 LED 5000 LUMENS, 3500K COLOR	KITCHEN CEILING LIGHTS. FURNISHED BY LICENSEE / INSTALLED BY G.C.
L1EM	L1EM	2X4 EDGE-LIT LED PANEL 120-277V UE - UNIVERSAL VOLTAGE	3	MANUFACTURER: LSI FIXTURE: SPF24-LED-50-UE-DIM-35 LED 5000 LUMENS, 3500K COLOR	EMERGENCY KITCHEN CEILING LIGHTS FURNISHED BY LICENSEE/ INSTALLED BY GC
		NOT USED	0		
L2	L2	2X2 EDGE-LIT LED PANEL (SURFACE MOUNT) 120-277V UE - UNIVERSAL VOLTAGE	2	MANUFACTURER: LSI FIXTURE: SPF24-LED-50-UE-DIM-35 LED 5000 LUMENS, 3500K COLOR	KITCHEN CEILING LIGHTS. FURNISHED BY LICENSEE / INSTALLED BY G.C.
L4	L4	UNIVERSAL MOUNT EXIT SIGN, LED LIGHTED, 120V WITH BATTERY PACK, 2 FACE, GREEN LETTER	2	JUNO, NAVILTE, NIBLHO THERMOPLASTIC EMERGENCY LIGHT	EXIT SIGN FURNISHED BY G.C./ INSTALLED BY GC
L6B	L6B	WALK-IN COOLER FLUORESCENT LIGHT, 120 V 48"	2	KASON FIXTURE: # 18180F00048	FURNISHED BY WIC VENDOR, INSTALLED BY G.C.
L19	L19	DOWN LIGHT, RECESSED IN CEILING	10	ELITE HOUSING: LD6IC-AT LED MODULE: ELITE LED LIGHTING RL607-14W-120-FL-27K-W-WH	FURNISHED BY LICENSEE/ INSTALLED BY GC
L19EM	L19 EM	EMERGENCY DOWN LIGHT, RECESSED IN CEILING	1	ELITE HOUSING: LD6IC-AT LED MODULE: ELITE LED LIGHTING RL607-14W-120-FL-30K-SN-SN	EMERGENCY RECESSED DOWN LIGHT - NORMALLY ON INVERTER UNIT - ISOLITE, IMI-12-LC-V1 FURNISHED BY LICENSEE/ INSTALLED BY GC
L6A	L6A	HOOD LIGHT	10	FURNISHED & INSTALLED BY EQUIPMENT SUPPLIER	LIGHTS SUPPLIED & PRE-WIRED BY HOOD VENDOR. ELECTRIC CONTRACTOR TO CONNECT MAIN WIRES TO SHUNT TRIP BREAKER AND HOOD CONTROL PANEL
L20	L20	LED MR16 DOWN LIGHT, RECESSED IN CEILING	1	HOUSING: LIGHTOLIER LYTECASTER 302MRSPX TRIM: LIGHTOLIER LYTECASTER 378WHX (WHITE) BULB: LED MR16 MANUFACTURER: GE PRODUCT CODE: 35535	
		NOT USED	0		

EQUIPMENT SCHEDULE

[THIS INFORMATION WAS PROVIDED BY THE OWNER & THE CONTRACTOR SHALL VERIFY ALL ELECTRICAL REQUIREMENTS w/ EQUIPMENT VENDOR(S) PRIOR TO ROUGH-IN OF POWER. NOTIFY ARCHITECT OF ANY CONFLICTS WITH-IN 10 DAYS OF EQUIPMENT APPROVAL.]

ELECTRICAL					DESCRIPTION					
D DIRECT CONNECTION					P PANDA EXPRESS VENDOR			S SERVING AREA		
C CONVENIENT OUTLET					GC GENERAL CONTRACTOR			K KITCHEN		
FSO FLOOR STUB OUT					EC ELECTRICAL CONTRACTOR			(E) EXISTING		
DC DROPPED CORD					KEC KITCHEN EQUIPMENT COMPANY			(L) LICENSEE		
CONNECTION	LOAD	PHASE	H.P.	VOLTS	REMARKS	DIMENSIONS	MANUFACTURE	MODEL #	EQUIPMENT	NO.
R.I.H. TYPE	WATT					W x D x H (ø x H)				
									SERVING AREA EQUIPMENT	
					SEE DETAIL	SEE PLAN	KEC	CUSTOM	HOT WELLS COUNTER, SERVICE	1B
					SEE DETAIL	SEE PLAN	KEC	CUSTOM	SNEEZE GUARD	1S2
REF. ELEC.	D 840W	1		120	3 HEATING ELEMENTS	43.06" X 5.25" X 3.03"	KEC		43" RADIANT TOP HEATER	1S2b1
	D 1100W	1		120	4 HEATING ELEMENTS	55.56" X 5.25" X 3.03"	KEC		56" RADIANT TOP HEATER (2)	1S2b2
	D 15A	1		120	SEE DETAIL	SEE PLAN	KEC	CUSTOM	CASHIER & BEVERAGE COUNTER	2Q
	C 650W	1		120	INDUCTION DRY WELL	15 3/4" DIA X 11"D	IO CONTROLS	IDW650L	INDUCTION WELL - 17QT	3F
	C 650W	1		120	INDUCTION DRY WELL	12 1/2" DIA X 11"D	IO CONTROLS	IDW650S	INDUCTION WELL - 11QT	3G
									KITCHEN EQUIPMENT	
					SEE DETAIL	93"x42"	KEC	CUSTOM	93" CHINESE RANGE (L)	20A
					SEE DETAIL	42"x42"	KEC	CUSTOM	42" CHINESE RANGE	20Q
24" C		1		120		47"x31-1/2"x51-5/8"	FRYMASTER	FMJ350-PE	FRYER	21A
36" DC	25A	3		208V		36"X27 7/8"X15 1/2"	STAR	536TGF	36" ELECTRICAL GRILL	23B
24" C	14.8A	1		120	NEMA 5	19.9"X34.5"X41.3"	WINSTON	HA4005	RICE HOLDING CABINET	24Hr
						19"#x17"	RINNAI	RER-55AS	RICE COOKER	25A
82" C	6.3A	1	1/2	115	NEMA 5-15P	52"X32"X83"	RANDELL	R2F-52-2	2-DR UPRIGHT FREEZER	30D
24" C	12A	1	1/2	115	NEMA 5-15P	48"X30"X29 3/4"	RANDELL	65348-290	48" WORKTOP FREEZER	30J
130" D	500W	1	1.5	120/208		SEE PLAN	GRE	CUSTOM	WALK-IN COOLER UNIT	31M
D	10.0A	1	1.5	208		INST. ABOVE W.I.BOX	GRE	CUSTOM	WALK-IN COOLER COND.	31-S
24" C	12A	1	1/2	120	SELF CONTAINED	84"x33"x35"	RANDELL	9050K-7MP2-NSB	84" REF. PREP. TABLE	34Oln
24" C	9A	1	1/3	120	SELF CONTAINED	48x33"x35"	RANDELL	9030K-7	48" REF. PREP. TABLE	34Dn
						100"x30"	KEC	CUSTOM-(PS-100L)	POT SINK	40A
					2 COMPARTMENT	72"x30"	KEC	CUSTOM-(VS-72)	72" VEGETABLE SINK (R)	41
18GA POLISHED (WALL MTD. @ 59" A.F.F.)						SEE PLAN	KEC	CUSTOM (NSF)	12"D S.S. WALL MTD. SHELF	43A
18GA POLISHED (WALL MTD. @ 71" A.F.F.)						SEE PLAN	KEC	CUSTOM (NSF)	16"D S.S. WALL MTD. SHELF	43B
4 SHELVES MTD. @ 8" A.F.F., 26" A.F.F., 54" A.F.F., 72" A.F.F.						SEE PLAN	GOLD BOND	ISS	18"D WIRE SHELVES	44A
4 SHELVES MTD. @ 36" A.F.F., 48" A.F.F., 60" A.F.F., 72" A.F.F.						SEE PLAN	GOLD BOND	ISS	24"D WIRE SHELVES	44C
						24"x 30" x 24"	KEC	CUSTOM	S.S. RICE COOKER STAND	46A
						36 1/2"x 33" x 28"	KEC	CUSTOM	S.S. GRILL STAND	46K
50" C	2.8A	1	1/3	120		12 1/2"x21"	PIPER	GSM-4	FOOD PROCESSOR	53
									SMALL EQUIPMENT	
					W/TOWEL & SOAP	SEE PLAN	CUSTOM	CUSTOM	ISLAND HAND SINK	7F
					W/TOWEL & SOAP	14 1/4"x18 1/2"	GSW	HS-1615NPASS	HAND SINK	45A
24" C	105W	1		120	ON S.S. COUNTER	17" ø	WELBON	WRS-1088BS	RICE WARMER	54A
84" DC	1800W	1		208	PLUG: NEMA 6-15R	17 1/2"X13 5/8"X22 9/16"	SHARP	R-CD1800M	MICROWAVE	55A
					AS REQUIRED BY LOCAL FIRE DEPT., CHECK LOCATION WITH PROJECT MANAGER				FIRE EXTINGUISHER	56
						SEE DETAIL	SAN-JAMAR	SANJT7500TBK	PAPER TOWEL DISPENSER	60D
					WALL MOUNT	12"x15"x78"	GRE	5-TIER	LOCKER (2)	61B
									SS LOW EQUIPMENT SCREEN WALL	B2M
									POS EQUIPMENT	
					SEE ELEV. ON E-200	48" X 28" X 42"	GRE	CUSTOM	MANAGER STATION	49A
REF ELEV C	100W	1		120	SEE DETAIL			CUSTOM	COMPUTER	83A
REF ELEV C	50W	1		120	SEE PLAN				POS PRINTERS	86A
REF ELEV C	50W	1		120					FAX	87
REF ELEV C	500W	1		120	CUSTOM	11 1/4"x14 1/2"x9"	RESNOS	S 460	CASH REGISTER SYSTEM	94
									MEP EQUIPMENT	
					SEE MECH. DWG.	SEE PLAN	CAPTIVE AIR	CUSTOM	EXHAUST HOOD	M1
					SEE MECH. DWG.	SEE PLAN	CAPTIVE AIR	CUSTOM	HOOD CONTROL PANEL	M4
					SEE MECH. DWG	SEE PLAN	CAPTIVE AIR		FIRE SUPPRESSION SYSTEM	M5
					SEE MECH/ELEC DWG	SEE PLAN			RECESSED ANSUL PULL BOX	M6
D					FLOOR TYPE	24" X 24" X 13"	C.S.W. PHONE:1800-897-5999	SE2424FM	STAINLESS STEEL MOP SINK	P1
87" C		1		120	SEE PLUMBING DWG	TANKLESS	RINNAI	SEE PLBG PLAN	TANKLESS WATER HEATER	P2
48" C	50W	1		120	SEE PLAN	15" X 13"	DELL (17" COLOR)		LCD MONITOR-MANAGER	94-2-16
					SEE ELEC. DWG			NEW	ELECTRICAL PANEL	E7
									SIGNAGE	
REF ELEV C	130W	1		120	DEDICATED CIRCUIT	48.9" X 28.1" X 1.3"	LG	55WS50BS-B	LCD DISPLAY MONITOR	96-3A
								SEE SIGN BOOK	LOCK-UP LOGO	S1
								SEE SIGN BOOK	LETTER SET SIGNAGE	S2

PANDA RESTAURANT GROUP INC.
1683 Walnut Grove Ave.
Rosemead, California
91770
Telephone: 626.799.9898
Facsimile: 626.372.8288

All ideas, designs, arrangement and plans indicated or represented by this drawing are the property of Panda Express Inc. and were created for use on this specific project. None of these ideas, designs, arrangements or plans may be used by or disclosed to any person, firm, or corporation without the written permission of Panda Express Inc.

REVISIONS:

ISSUE DATE:

1	95% SUBMITTAL	01/11/2020
2	100% SUBMITTAL	04/16/2021
3	100% RESUBMITTAL	05/14/2021
4	FINAL SUBMITTAL	06/08/2021

DRAWN BY: JMJ

PANDA PROJECT #: D7395
ARCH PROJECT #:

MARSHALL & BOLLWERK ENGINEERING, INC.
8681 Highway 92, Suite 400
Woodstock, Ga. 30189
p: (678) 795-0333, f: (678) 325-4558
e: mbe@mbeinc.net

GEORGIA REGISTERED No. 30016 PROFESSIONAL ENGINEER MICHAEL JONES 12-29-2020

PANDA EXPRESS

ROBINS AFB SHOPPING CENTER
ROBINS AFB, GA

BID SET - 2021/06/28

E-001

ELECTRICAL SCHEDULES